






LOCUS NTS



SCHEMATIC PROFILE
N.T.S.



PUMP CURVE




TYPICAL LEACH BED SECTION
N.T.S.

DESIGN CRITERIA


- Estimated Hydraulic Loading
3 bedrooms at 110 gpd/bedroom = 330 gpd
Garbage disposal shall not be allowed with this system.
- Prop. Septic tank size = 1500 gallons.
Pump chamber size = 1000 gallons.
- Leaching Area Design Criteria
Percolation Rate = < 2 mpi
Soil Class Type = 1 (SAND)
Allowable Loading Rate = $\frac{0.74 \text{ gpd/sf}}{330 \text{ gpd}} = 0.0022 \text{ gpd/sf}$
Required Leaching Area = $\frac{330 \text{ gpd}}{0.0022 \text{ gpd/sf}} = 150,000 \text{ sq ft}$
Leaching Area Provided = $1 \text{ bed} \times 38 \text{ ft bed length} \times 12 \text{ ft bed width} = 456 \text{ sq ft}$
- Breakout
Breakout Elevation = 98.6
Breakout Distance = 15 ft (5' w/ barrier)
Distance Provided = 5 ft

LEGEND

- 242 EXISTING CONTOUR
- 242 PROPOSED CONTOUR
- TP-1 DEEP HOLE TEST PIT
- PT-1 PERCOLATION TEST
- + 238.6 SPOT ELEVATION
- W WATER SERVICE



CONCRETE BLOCK BREAKOUT WALL DETAIL



PLAN 1=20'

GENERAL NOTES

- Unless otherwise noted, property lines shown are compiled from existing plans and deeds of record.
- Underground utility data is plotted from visible field locations and available records. The locations are approximate only and verification must be made in the field.
- All construction to conform to 310 CMR 15.000, "The State Environmental Code, Title 5" and the Board of Health requirements for the Town of Winchendon.
- The contractor shall install the system exactly as shown on this plan. If changes are necessary, the contractor must contact the Engineer in advance.
- Heavy machinery shall not be permitted to pass over the leaching area and the contractor shall stake and flag the soil absorption/leaching area perimeter upon completion.
- All piping shall be polyvinyl chloride (PVC) pipe per ASTM D1785 for SCH. 40 and ASTM D3034 for SDR 35 where indicated on the profile, unless otherwise noted.
- Pump chamber shall be a 1000 gallon reinforced concrete tank of H-10 load design (min.) and watertight conforming to all of the requirements of 310 CMR 15.221, 15.223, 15.226, 15.227, 15.228.
- The distribution box (D-box) shall be a 5 outlet reinforced concrete box of H-10 load design (min.) with a watertight cover and conform to all the requirements of 310 CMR 15.232.
- All topsoil, subsoil and impervious material, if any, must be excavated and removed below and 5' beyond the soil absorption system area. Fill material shall consist of a clean granular sand, free from organic matter and deleterious substances. Mixtures and layers of different classes of soil not be used. The sand fill shall not contain any material larger than 2 inches. A sieve analysis, using a #4 sieve, shall be performed on a representative sample of the fill. Up to 45% by weight of the fill sample may be retained on the #4 sieve. Sieve analyses also shall be performed on the fraction of the fill sample passing the #4 sieve, such analyses must demonstrate that the material meets or exceeds each of the following specifications: 100% passing #4 sieve; 10%-100% passing #50 sieve; 0%-20% passing #100 sieve; 0%-5% passing #200 sieve. (11/95 DEP SPEC)
- For proper performance, septic tank should be inspected at least once a year and pumped when the top of the sludge or solids layer is within 12" or less of the bottom of the outlet tee or the bottom of the scum layer is within 2 inches of the bottom of outlet tee (every 2 or 3 years).
- There are no wells located within 100 feet of the proposed system.
- An RDA/NOI is required to be filed with the conservation commission for the work shown hereon.
- Much of the back yard is occupied by old septic systems, these systems shall be removed/abandoned per 310 CMR 15.354. Leach field in location of proposed septic system shall be removed and the area excavated to the native C soil.
- Existing dwelling listed as a 2-bedroom on town tax cards, however appears to have operated as a 3-bedroom dwelling since an addition was constructed before 1974.

SOIL TEST DATA

DEEP HOLE TESTS		PERC TESTS	
PERFORMED BY: TREVOR FLETCHER, P.E.		TREVOR FLETCHER, P.E.	
WITNESSED BY: JAMES ABARE, B.O.H. WINCHENDON		JAMES ABARE, B.O.H. WINCHENDON	
DATE: MARCH 20, 2023		DATE: MARCH 20, 2023	
DEEP HOLE # TP-1	DEEP HOLE # TP-2	DEEP HOLE # TP-3	DEEP HOLE # TP-4
FSL 0"	FSL 0"	FSL 0"	FSL 0"
10YR 2/2 A	10YR 2/2 A	10YR 2/2 A	10YR 2/2 A
12" LOAMY SAND	12" LOAMY SAND	12" LOAMY SAND	12" LOAMY SAND
10YR 4/6 B	10YR 4/6 B	10YR 4/6 B	10YR 4/6 B
16"	16"	16"	16"
SAND 10YR 4/6 C	SAND 10YR 5/8 C	SAND 10YR 5/8 C	SAND 10YR 5/8 C
21"	21"	21"	21"
66"	66"	78"	74"
ESHWT @ 24"	ESHWT @ 26"	ESHWT @ 34"	ESHWT @ 34"
GRD EL 95.1	GRD EL 95.4	GRD EL 95.1	GRD EL 95.2
ESHWT @ EL 93.1	ESHWT @ EL 93.2	ESHWT @ EL 92.3	ESHWT @ EL 92.4
REFUSAL EL NA	REFUSAL EL NA	REFUSAL EL NA	REFUSAL EL NA

PERC TEST NUMBER	DEPTH	PERC RATE	NOTES
PT-1	36"	< 2 MPI	
PT-2	34"	< 2 MPI	

NO.	DESCRIPTION	DATE	BY



DESIGNED BY TWF
DRAWN BY TWF
CHECKED BY PFG
DATE MARCH 29, 2023
SCALE AS NOTED
JOB NUMBER 23130

PROPOSED SEPTIC SYSTEM EXPANSION DESIGN
12 BALDWINVILLE STATE ROAD (MAP-7A4 LOT-57)
WINCHENDON, MASSACHUSETTS
PREPARED FOR
TRACI A. DOIRON
12 BALDWINVILLE STATE ROAD; WINCHENDON, MA 01475
GRAZ Engineering, LLC
323 WEST LAKE RD.; FITZ WILLIAM, NH 03447; (603) 585-6959
FIELD BOOK NO. PAGES
SHEET 1 OF 1